



ROTHESAY
STANDARDS & REQUIREMENTS for NEW CONSTRUCTION
Schedule "C"



BE IT RESOLVED THAT:

- 1) only a Sensus SR type Cold Water Meter or an Engineer-approved equal shall be installed, complete with a remote touchpad readout located on the exterior of the building, with said meter and remote readout supplied by the town of Rothesay at the time of application for a Building Permit and all associated installation costs borne by the property owner;
- 2) the following standard specifications shall apply as if written out in full herein and references to standards or codes shall mean the latest edition of such publication adopted and published at the date of application to connect to the water system:

CANADIAN PLUMBING CODE
CANADIAN STANDARDS ASSOCIATION
AMERICAN WATER WORKS ASSOCIATION
AMERICAN SOCIETY FOR TESTING MATERIALS

- 3) the following construction methods shall be followed:
 - 3.1 METERS: The property owner shall ensure the installation of the meter and associated equipment by a qualified licensed plumber and all meters shall be installed in a horizontal position with the register side facing upwards.
 - 3.2 FLUSHING: The inlet line shall be flushed prior to the installation of the water meter.
 - 3.3 PLACING INTO OPERATION: The property owner shall open the inlet shut-off valve slowly to allow the water meter to fill and trapped air to escape.
 - 3.4 LEAK TEST: All joints shall be leak tested and checked after the meter is placed into operation.
 - 3.5 REMOTE READOUT: The remote readout shall be installed on the exterior of the building on the driveway side of the building.
 - 3.6 WIRING: The property owner shall supply and install 18 gauge two conductor bell wire for use in connecting the meter with the exterior remote touchpad.
 - 3.7 VALVES: The property owner shall ensure the meter is isolated on either side of the meter.
 - 3.8 INSPECTION: The property owner shall permit and facilitate observation of the work by the town of Rothesay and its agents and public authorities at all times.

mpb
01/14/19